



NOTES:

1. Concrete to have 20 MPa in place strength at 28 days.
2. Concrete to be finished flush with surrounding surface.
3. All pipe work to be galvanised.
4. For PED handrail use alternative mounting detail.
5. Above ground tubing to be powder coated white.

PLAN
Example of location in walkway

